

CALL FOR QUOTATIONS/TENDERS: UP GRADATION OF MAIN GATE AT ARMY PUBLIC SCHOOL SENIOR WING, UDHAMPUR

Introduction

1. Army Public School, Udhampur invites offers in two bid system from established vendors for Up gradation of Main Gate at Army Public School Senior Wing, Udhampur.
2. For complete details and formats of RFP please log on to School's website www.apsudhampur.org. RFP forms can also be obtained from the school at the above address (Mobile : 9596881756) on payment of Rs 100/- (Non refundable) by way of demand draft/ pay order favouring Army Public School, Udhampur payable at Udhampur. However for RFPs downloaded from website, the pay order/ Demand draft should be submitted along with the commercial offer.

Tender Schedule

3. Schedule of events of various Tender related events is :

Ser No	Event	Date	Venue
(a)	Date of downloading RFP from the website	20 Mar 2019 onwards	Army Public School, Udhampur apsudhampur@gmail.com Mobile No 9596881756
(b)	Last date for receiving queries and comments	25 Mar 2019 at 1500 hrs	
(c)	Bidders are free to visit site between D plus 10 days and D plus 15 days.	25 Mar 2019 to 05 Apr 2019 at 1000 hrs	
(d)	Last date for submission of bid	10 Apr 2019 at 1500 hrs	
(e)	Date of opening of Technical bid and Commercial bid	11 Apr 2019 at 1100 hrs	

Note:

1. If any date specified herein is a holiday, then the next working day will be considered for the activity and the time will remain the same.
2. The Schedule indicated above is tentative and school may change any or the entire schedule under intimation to all bidders.
3. All conditions and parameters will be evaluated with reference to the firms submitting tenders. The school reserves the right to reject any/ all applications without assigning any reasons whatsoever. No brokers/ intermediaries shall be entertained.
4. Bids are invited for Up gradation of Main Gate at Army Public School, Senior Wing, Udhampur as specified below:-

Technical Bid

Tiling work in front of Main Gate. The Front of main gate needs to be up graded (Towards East side and West sides are indicated) as specified below:-

- (a) Removal of existing RCC floor towards East side of main gate 50 ft x 50 ft = 2,500 sq ft up to 4 ½ inch depth to make the surface even.
- (b) Earth work and leveling of ground towards East side of gate 62 ft x 65 ft = 4,030 sq ft.
- (c) Leveling of area towards west side of ATM(after drain) 87.5 ft x 31.2 ft = 2,730 sq ft.
- (d) Removal of waste material from site of work.
- (e) Providing and laying metal (Stone aggregate) in the ratio of 1:4:8. Approx area of metaling is 1,335 sq ft.
- (f) Providing and laying inter locking coloured tiles 3 Inch thick. Approx area of tiling is 7,766 sq ft.
- (j) Providing and laying Bajri in the ratio of 1:3:6 to fill gaps on sides wherever required.
- (k) Provision of labour, material, shuttering etc complete as per requirement.

Supply and Fixing of Main Gate: Existing Main Gate is required to be replaced with new Steel Gate as specified below:-

- (a) Existing double shutter gate is required to be replaced with new Steel Gate (double shutter) of size 8 ft height and 15.6 ft breadth. Total area will be 124.8 sq ft.
- (b) Single Shutter gate for persons walking on foot on right side of main gate of size 6.3 ft height and 3.4 ft breadth is also required to be replaced with new Steel gate. Total area of this gate works out to 21.42 sq ft.
- (c) Three images of new Steel gate are attached to this RFP. Each shutter of gate will have school logo with illumination.
- (d) Existing shutters of both the gates i.e. double shutter and single shutter are school property and will be taken back by the school.
- (e) Rollers will also be fixed in the gate for smooth opening and closing movement.
- (f) Height of two pillars will be increased by 2ft i.e. from 10 ft to 12 ft. Existing two pillars are of height 10 ft, length 2 ft 8 inch and breadth 1 ft 10 inch. Granite will also be fixed to 2 ft extended height which is approx 40 sq ft before fixing of ACP sheets. Existing one pillar is of height 6 ft 10 inch, length 1 ft 7 inch and breadth 1 ft 6 inch height of which will remain the same.
- (g) Aluminum frame of size 1 ½ " x 1" as required will be fixed in three pillars of the gate on required basis for fixing ACP sheets.
- (h) Existing three pillars of the gate are required to be covered with ACP Sheet of 3 mm thickness. Vendors are requested to check sample of ACP Sheet from the school before quoting the rates. Total area to be covered with ACP sheet works out as under:-

(ii) 2 x pillars of size 12 ½ ft x 9 ½ ft = 241.92 sq ft.	} Total: <u>283.32 sq ft</u>
(iii) 1 x pillar of size 6 ft 9 inch x 6 ft = 41.4 sq ft	

9. The address and contact numbers for sending bids or seeking clarifications regarding this RFP are given below:-

(a) Bids/queries to be addressed to : Principal, Army Public School, Udhampur.

(b) Postal Address for sending the bids: Army Public School, PO
PTA, Udhampur- 182104

(c) Name/ designation of the contact person: Sanjeev Kumar,
Principal, APS, Udhampur.

(d) Telephone number : Mil : 2167, Mobile : 9596881756

(e) E-mail id: apsudhampur @ gmail.com

10. No boarding and lodging for the construction team will be provided inside School premises due to security reasons.

11. 10% of tendered amount will be deducted as defect liability. This amount will be retained by the school and will be released after defect liability period of one year.

12. 2% of tendered amount will be deducted as TDS as per Income Tax rules.

13. This RFP is being issued with no financial commitment and the customer reserves the right to change or vary any part thereof at any stage. Buyer also reserves the right to withdraw the RFP, should it become necessary at any stage.

Yours faithfully,



Principal