

CALL FOR QUOTATIONS/TENDERS :

**CONSTR OF CONVENIENCE ROOM FOR BOYS AND GIRLS NEAR TUCK SHOP
OF APS UDHAMPUR**

Introduction

1. Army Public School, Udhampur invites offers in **two bids system** from the authorized dealers/vendors for the project "**Constr of Convenience Room for Boys & Girls near Tuck Shop of APS Udhampur**".

2. Bids are invited for the project as specified below:-

S No	Details	A/U	Qty
(a)	(i) Clean and leveling the existing area near Tuck Shop and dismantling of existing brick structure of water tank. (ii) Constr of New Convenience room for Boys (size 10 x 18 ft & Height - 10 ft) , and Girls (size 10 x 18 ft & Height - 10 ft) , brick masonry work with GI colour coated sheet roofing (3 ft both side slop with PVC Pipe holding rain water for proper drain), Powder coated Aluminium doors and ventilation, false ceiling, electrical work and sanitary fitting as per specification. Plinth up to 2 ft above ground with brick stairs in front of doors. Centre wall of both the convenience room is common. 4 ft height L Shape structure in front of door. (iii) Constr of 01 x new Septic Tank (8 x 8 x 10 ft) with concrete & TMT slab and soak pit.	Nos	01 (10 x 18 ft) for Boys 01 (10 x 18 ft) for Girls

Technical Specification

Boys Convenience Room

S. NO	Description of Item	Qty
1	Earth work of foundation and re filling of excavation of earth etc.	1200 cft
2	Construction of New Brick work in foundation and superstructure above plinth level in all side new brick work.	1160 cft
3	Half Brick work 1:4 cement mortar	410 sqft
4	12 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand)	2001 sqft
5	Laying of cement concrete for levelling of plinth level: 1:3:6	210 cft
6	Laying of New RCC plinth beam and lintel beam 1:1.5:3	105 cft
7	Cantering and shuttering of New plinth & lintel beam etc.	650 sqft
8	Steel reinforcement for New R.C.C. work	750 kg
9	Making plinth protection 50 mm thick of cement concrete 1:3:6 over 75mm thick	160 sqft
10	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc	1850 sqft
11	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by in-charge)	460 sqft
12	Supply & fixing of Vitrified tiles in floor in different sizes floor tiles of size 600x600 of approved make	226 sqft
13	Supply & fixing of 1st quality ceramic glazed wall tiles of approved make (4x2 ft) (Internal walls)	1450 sqft
14	Stone tile work for wall lining with special adhesive over 12 mm thick bed of cement mortar 1:3 (External wall) (1x1.5 ft)	560 sqft

S. NO	Description of Item	Qty
15	PVC heavy duty drain pipe pitting for toilet seat, wash basin, and urinal system complete work: 110 & 75 mm bore pipe	110 rft
16	Fixing (CPVC) pipes, water supply including all CPVC plain & brass threaded fittings and complete work: 15 and 20 mm	368 rft
17	Fixing square-mouth S.W. gully trap class SP-1 complete brick masonry chamber	2 Nos
18	P/L cement concrete (1:5:10) up to haunches of 110 mm & 75 mm PVC drain pipe	86 rft
19	S/F powder coated aluminium doors, windows, ventilators with extruded built up standard tubular sections and other sections of approved make, all complete openable door frame & shutter etc.	108 sqft
20	Fixing ACP sheet 3mm thick in aluminium door, shutters with EPDM rubber / neoprene gasket etc	88 sqft
21	S/ F aluminium sliding door bolts, size 300x 16mm, ISI marked	6 Nos
22	S/F aluminium tower bolts, size 200x10mm, ISI marked	6 Nos
23	S/F aluminium handles, size 150 mm ISI marked	12 Nos
24	S/F aluminium die cast body tubular type universal hydraulic door closer, earl with inbuilt locks	01 Nos
25	S/F tiled false ceiling of approved materials of size 595x595	220 sqft
26	S/F white Vitreous china Orissa pattern (Indian type W.C. pan) complete all fitting.	02 Nos
27	S/F white Vitreous English seat complete all fitting	01 Nos
28	S/F 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled	03 Nos
29	S/F China flat back half stall urinal of size 580x380x350 mm with white PVC automatic flushing complete all fitting	05 Nos
30	S/F white Vitreous China Wash basin size 550x400 mm with pedestal complete fitting.	02 Nos
31	S/F of white vitreous urinal partition	04 Nos
32	S/F CP Bib tap/ pillar cock/ angle valve (fancy type) 15 mm	12 Nos
33	S/F CP Concealed stop cock extra heavy body with adjustable wall flange	10 Nos
34	S/F CP soap dish/ shop container	02 Nos
35	S/F CP towel ring complete with all respect	02 Nos
36	S/F CP Grating Doom 100 mm dia, fixed in floor	12 Nos
37	S/F good quality of Glass mirror 600x450 mm	02 Nos
38	S/F CP jet complete fitting	02 Nos
39	S/F CP fittings paper holder	02 Nos
40	S/F cp cup complete fitting	18 Nos
41	Constructing brick masonry manhole in cement mortar 1:4 (1cement : 4 coarse sand) with R.C.C. top slab	01 Nos
42	Supply and fixing 2000 lit cap. PVC water tank and steel structure frame work up to 15 feet complete fitting.	01 Nos
43	Wiring for light point/ exhaust fan point with 1.5 sq.mm FR PVC insulated copper conductor single core cable	8 Nos
44	S/F PVC insulated copper conductor, single core 2 x 1.5 sq.mm + 1 x 1.5 sq. mm earth wire	600 Rft
45	S/F PVC conduit along with accessories in surface/recess 20 mm dia	300 Rft
46	metal box of following sizes (nominal size) on surface 200 mm X 150 mm X 60 mm deep	02 Nos
47	Modular type switch & socket 5/15 Amp compatible	12 Nos
48	LED type light 20 W-230V, with complete fitting	02 Nos
49	Exhaust fan heavy duty 300 mm sweep with louvers	01 Nos
50	Supplying and fixing 5 amps to 32 amps rating	04 Nos
51	Supplying and fixing of 2'x2' 36 watt LED false Ceiling light	04 Nos

Girls Convenience Room

S. NO	Description of Item	Qty
1	Earth work of foundation and re filling of excavation of earth etc.	1200 cft
2	Construction of New Brick work in foundation and superstructure above plinth level in all side new brick work and 4 ft height L shape structure in front of door.	1160 cft
3	Half Brick work 1:4 cement mortar	410 sqft
4	12 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand)	2001 sqft
5	Laying of cement concrete for levelling of plinth level: 1:3:6	210 cft
6	Laying of New RCC plinth beam and lintel beam 1:1.5:3	105 cft
7	Cantering and shuttering of New plinth & lintel beam etc.	650 sqft
8	Steel reinforcement for New R.C.C. work	750 kg
9	Making plinth protection 50 mm thick of cement concrete 1:3:6 over 75mm thick	160 sqft
10	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc	1850 sqft
11	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by in-charge)	460 sqft
12	Supply & fixing of Vitrified tiles in floor in different sizes floor tiles of size 600x600 of approved make	226 sqft
13	Supply & fixing of 1st quality ceramic glazed wall tiles of approved make (4x2 ft) (Internal walls)	1450 sqft
14	Stone tile work for wall lining with special adhesive over 12 mm thick bed of cement mortar 1:3 (External wall) (1x1.5 ft)	560 sqft
15	PVC heavy duty drain pipe pitting for toilet seat, wash basin, and urinal system complete work: 110 & 75 mm bore pipe	110 rft
16	Fixing (CPVC) pipes, water supply including all CPVC plain & brass threaded fittings and complete work: 15 and 20 mm	368 rft
17	Fixing square-mouth S.W. gully trap class SP-1 complete brick masonry chamber	02 Nos
18	P/L cement concrete (1:5:10) up to haunches of 110 mm & 75 mm PVC drain pipe	86 rft
19	S/F powder coated aluminium doors, windows, ventilators with extruded built up standard tubular sections and other sections of approved make, all complete openable door frame & shutter etc.	108 sqft
20	Fixing ACP sheet 3mm thick in aluminium door, shutters with EPDM rubber / neoprene gasket etc	88 sqft
21	S/ F aluminium sliding door bolts, size 300x 16mm, ISI marked	6 Nos
22	S/F aluminium tower bolts, size 200x10mm, ISI marked	6 Nos
23	S/F aluminium handles, size 150 mm ISI marked	12 Nos
24	S/F aluminium die cast body tubular type universal hydraulic door closer	01 Nos
25	S/F tiled false ceiling of approved materials of size 595x595	220 sqft
26	S/F white Vitreous china Orissa pattern (Indian type W.C. pan) complete all fitting.	02 Nos
27	S/F white Vitreous English seat complete all fitting	02 Nos
28	S/F 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled	04 Nos
29	S/F white Vitreous China Wash basin size 550x400 mm with pedestal complete fitting.	02 Nos
30	S/F CP Bib tap/ pillar cock/ angle valve (fancy type) 15 mm	14 Nos
31	S/F CP Concealed stop cock extra heavy body with adjustable wall flange	12 Nos
32	S/F CP soap dish/ shop container	02 Nos

S. NO	Description of Item	Qty
33	S/F CP towel ring complete with all respect	02 Nos
34	S/F CP Grating Doom 100 mm dia, fixed in floor	14 Nos
35	S/F good quality of Glass mirror 600x450 mm	02 Nos
36	S/F CP jet complete fitting	02 Nos
37	S/F CP fittings paper holder	02 Nos
38	S/F cp cup complete fitting	18 Nos
39	Constructing brick masonry manhole in cement mortar 1:4 (1cement : 4 coarse sand) with R.C.C. top slab	01 Nos
40	Supply and fixing 2000 lit cap. PVC water tank and steel structure frame work up to 15 feet complete fitting.	01 Nos
41	Wiring for light point/ exhaust fan point with 1.5 sq.mm FR PVC insulated copper conductor single core cable	08 Nos
42	S/F PVC insulated copper conductor, single core 2 x 1.5 sq.mm + 1 x 1.5 sq. mm earth wire	600 Rft
43	S/F PVC conduit along with accessories in surface/recess 20 mm dia	300 Rft
44	Metal box of following sizes (nominal size) on surface 200 mm X 150 mm X 60 mm deep	02 Nos
45	Modular type switch & socket 5/15 Amp compatible	12 Nos
46	LED type light 20 W-230V, with complete fitting	02 Nos
47	Exhaust fan heavy duty 300 mm sweep with louvers	01 Nos
48	Supplying and fixing 5 amps to 32 amps rating	04 Nos
49	Supplying and fixing of 2'x2' 36 watt LED false Ceiling light	04 Nos

Septic Tank

S No	Item	Description
1.	Type	RCC on-site Septic Tank
2.	Size	Length: 10 ft, Width: 8 ft, Depth: 8 ft (usable depth after slab)
3.	Capacity	Approx. 4,500–5,000 liters – suitable for 30–40 users/day
4.	Wall	Brick walls
5.	Base Slab	6" (150 mm) RCC with 1:2:4 mix
6.	Top Slab	RCC slab with 2 manholes (18" dia) for cleaning
7.	Plastering	Internal cement plaster 12 mm thick with waterproofing compound
8.	Waterproofing	Integral waterproofing treatment with admixture like Dr. Fixit or equivalent
9.	Vent Pipe	100 mm (4") dia PVC or GI vent pipe extended 2 feet above roof level with fly mesh and cowl
10.	Slope	Inlet pipe at 1 in 40 slope, outlet slightly lower for free flow
<u>Sewage Connectivity & Overflow Arrangement</u>		
11.	Inlet Pipe	100 mm (4") dia PVC pipe connected from toilet blocks at 1 in 40 gradient
12.	Outlet/Overflow Pipe	100 mm (4") dia PVC pipe connected to soak pit or municipal sewer/drain
13.	Soak Pit	Circular pit 4 ft dia, 6 ft deep, filled with brick ballast, sand, and stones; RCC cover slab on top
14.	Waste water	To be connected with nearest drainage system

Approved Material to be used.

S. No	Materials	Approved Make / Manufactures
1.	Cement	ACC, Ambuja, Birla, Bangur L&T, Ultra-Tech. Shree-Ultra,
2.	CP Brass Sanitary fittings/ Accessories	Jaquar/Cera/Prayag

S. No	Materials	Approved Make / Manufactures
3.	Orissa Pan, W.C, Vitreous and wash basin, Urinal etc.	Hindware, Orient, Cera, Paryware
4.	Ceramic Tiles/ Vitrified Tiles	Kajaria, Nitco, Orient, Somany, Jonhson
5.	Mild steel Bar / TMT bar/ Angle Iron	SAIL, TATA, RINL, Jindal, Kamdhnu
6.	Cast Iron Pipes & Fittings Manhole Covers and Frames	Bajaj, MES, NECO, BIC Calcutta, Kajeco,
7.	M. S. Pipe & accessories	TATA, SAIL, RINL, Jindal
8.	G. I. Pipe & accessories	Jindal, Prakash surya, TATA
9.	G. I Fitting	UNIK, DRP-M, KENT, ZOLOTO-M
10.	Gate/ wheel valve/ Gun metal valves	Leader, DRP, ZOLOTO
11.	OBD, emulsion, Primer synthetic Paint materials etc.	Asian, Nerolac, Dulux
12.	Pre-Coated iron Galvanized profile sheet and accessories	Jindal, TATA
13.	PTMT fitting	Prayag, Praksh Surya, Hindware, Cera, Parryware
14.	18mm/12mm/6mm /4mm Ply Board	Confore, Garnix, Century, Douro
15.	Mica	Mirrino, Greenlam, Kitlam
16.	Water Storage Tank	Sintex (Tripal Layer)
17.	Looking mirror	Atul/Modi auard/Saint Gobian

List of Approved Makes (Electricals Works)

S.No	Materials	Approved Make / Manufactures
1	Flexible Copper wires	Finolex/ Havell's/ Polycab wires / Shalimar (FR)
2	Switch & Sockets	Legrand/ Anchor/ Havells/ ABB
3	Distribution board	Legrand/ Hager/ Havell's
4	MCCB, MCB, RCCB	Legrand/ Hager/ Havell's/ L&T.
5	Casing caping/Conduit	Berlia/ Polypack/ Pestoplast/ Richa / Setia (2 mm)
6.	Exhaust fan	Bajaj/ Crompton Greaves/ Havells/ Usha/Orient
7.	Lighting fixture	Phillips/ Bajaj/ Crompton/Havells/Wipro
8.	Ceiling fan	Bajaj/ Crompton Greaves/ Havells/ Usha/Orient
9.	BUS BARS / Panels	CPRI Approved
10.	Cables	Armoured/ Havells / Polycab/ (ISI Approved)

Note - Interested bidders must visit the site and check scope of work physically for any query before quoting their bids.

3. **Eligibility criteria**

Technical Bid :

- Technical Specification to be attached
- GST Registration Certificate.
- Latest Qtr/month GST return should be attached.
- PAN Card Copy should be attached.
- Last one year IT return should be attached.
- Experience Certificate in the field of the tender.
- EMD / Submit MSME Certificate.

Commercial Bid

- Prices of the items should be inclusive of GST.
- However, quoted price should include cost of material, transportation, installation and labour charges incurred to make the items functional in the school premises.
- Any variation in warranty period other than specified in Para 13 of this Call for Quotation should invariably highlighted separately.

4. Technical Bid and Commercial Bid given above need to be sealed in two separate envelopes and these two bids put in a single envelope and write on top of the single envelope **“Technical and Commercial Bids inside in this envelope”**.

Technical Bid और Commercial Bid दो अलग-अलग लिफाफे में रखकर, एक बड़े लिफाफे में डालें और उस बड़े लिफाफे पर लिखें :-

“Technical Bid and Commercial Bid Inside in this envelope”

5. Bids in sealed cover are invited for **“Constr of Convenience Room for Boys & Girls near Tuck Shop of APS Udhampur”**. The vendors/ dealers having proper valid GST Number may submit their bids. Please super scribe “_____ (type of bid) **“Constr of Convenience Room for Boys & Girls near Tuck Shop of APS Udhampur”**”. RFP number i.e 1058/APSU and date of opening of the bids i.e. **23 Sep 2025** on the sealed cover to avoid the bid being declared invalid.

6. (a) Last date for submission of bids by **1500 hrs on 22 Sep 2025**. The sealed bids should be reached by the due date and time. The responsibility to ensure this lies with the bidder. Bids received beyond the time and date given above shall be rejected.

(b) **Manner of depositing the bids**: Sealed bids should be sent by **Registered Post / Courier only** at the address mentioned in **Para 20 below** so as to reach by the due date and time. No responsibility will be taken for postal delay or non delivery/ non receipt of bid documents. Bids sent by FAX or e-mail or deposit by himself in Tender Box will not be considered (unless the latter has been specifically called for by these modes due to urgency).

(c) **Time and date for opening of bids** : **23 Sep 2025 at 1100 hrs at APS, Primary Wing, Udhampur** onwards. (if due to any exigency or the due date for opening of the bids is declared closed holiday, the bids will be opened on the next working day at the same time or on any other day/time).

(d) **Earnest Money Deposit**: Bidders are required to submit Earnest Money Deposit (EMD) of **Rs 20,000/-** in the name of Principal, APS Udhampur along with their **technical bid/ submit MSME Cert only**. The EMD should be submitted in the form of Fixed Deposit Receipt (FDR), Call Deposit Receipt (CDR) or cheque from any of the public sector banks or a private sector bank authorized to conduct government business.

(e) **Technical Bid received without EMD / MSME Cert will be rejected.**

Special conditions

7. **Payment Terms**: It will be mandatory for the bidders to indicate their Bank Account numbers and other relevant payment details in bill so that payments could be made through cheque.

8. **Full payments shall be made on completion of the full order as specified**, after inspection and acceptance of items for quality, completeness and serviceability by the Board detailed by the purchaser. Payment will be made for the complete order and not in parts.

9. Payment would be made through interbank transfer once the Acceptance has been issued by BOO after receipt, installation and commissioning of stores at loc which will be given in Supply Order. No advance payment is admissible.

10. **Paying Authority** : Army Public School, Udhampur after prior approval of Competent Financial authority.

11. **Quality:** The quality of the stores delivered according to the present Contract shall correspond to the technical conditions and standards valid for the deliveries of the same stores or specifications enumerated as per RFP and shall also include therein Modification to the stores suggested by the Buyer. Such modifications will be mutually agreed to. The Seller shall supply an interchangeability certificate along with the changed part numbers wherein it should be mentioned that item would provide as much life as the original item.

12. **Inspection Authority :** The inspection will be carried out by bd of Officers detailed by the school management.

13. **Warranty :** The Seller will provide free comprehensive warranty for a period of minimum **10 years** from the date of acceptance of stores by the bd of officers detailed by the school management or date of installation and commissioning, whichever is later that the goods/stores supplied under the contract and each component used in the manufacture thereof shall be free from all types of defects/failures. During warranty period the vendor shall repair/replace without extra cost any equipment/part/accessory that becomes except defective items of a consumable nature.

14. **Liquidated Damages:** Liquidated Damages (LD), if the Seller fails to deliver the stores in full, within the stipulated period from the date of the supply/installation order, he shall pay the CUSTOMER liquidated damages, at the rate of one percent (1%) of the total value of the supply order for each completed week or part there of up to a maximum of ten percent (10%) of the value of undelivered stores of supply/installation order. This payment will be made through demand draft or MRO in favour of Army Public School, Udhampur. Thereafter the CUSTOMER will have right to terminate the supply order in the case of such delay beyond 10 weeks and the customer would have the option to buy the items and accessories from the market at the vendors risk and cost. The mode of risk purchase would be the total discretion of the customer i.e. Principal Army Public School, Udhampur.

General.

15. **Jurisdiction.** The Court of the place from where the acceptance of tender has been issued shall alone have jurisdiction to decide any dispute arising in respect of the contract.

16. No Litigation/Arbitration under any circumstances at any stage is applicable, the decision of Principal/ Mgt Body of Army Public School, Udhampur will be final and binding in all respect.

17. **Ownership Title:** The ownership of all the items being supplied will be with Principal Army Public School, Udhampur. All document and registration details to this effect will be handed over by the vendor at the time of delivery.

18. **Manual and Literature.** All related manuals, literature and Test certificate for the items supplied will also be handed over with the equipment.

19. No insurance charges will be paid by the school. Consignee accept no responsibility of liability for the loss of damage of the storage in transit of the rejected stores lying inside the school premises for reasons whatsoever.

20. The address and contact numbers for sending bids or seeking clarifications regarding this RFP are given below :-

(a) Postal Address :-

**Coordinator
Army Public School
Primary Wing, Udhampur
PO - Garhi
Tehsil & Dist - Udhampur (Jammu & Kashmir)
Pin - 182121**

(b) Telephone number : **01992-295370** & Mobile : **9596881756**

(c) E-mail id: **apsudhpurchase@gmail.com**

21. No boarding and lodging for the installation team will be provided inside School premises due to security reasons.

22. This RFP is being issued with no financial commitment and the customer reserves the right to change or vary any part thereof at any stage. Buyer also reserves the right to withdraw the RFP, should it become necessary at any stage.

23. **10% of the tender amount will be retained by the school as security of defect liability which will be released after defect liability period of one year. This amount will be deducted from tendered amount**

24. Income tax payment will be vendor's liability. 1% TDS will be deducted as per IT Rules.



(Dr Sanjeev Kumar)
Principal